

DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

MODIFIED SCHDULE-B**Name of Work: Estimate for providing Rain water harvesting in ward No 15
Dasarahalli Sub division**

Job Code: 015-20-000012					
Sl	Description of Work	Unit	Qty	Sanctioned Rates	
				In figures (Rs)	In Words (Rs)
1	KSRRB300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. Page No-143 , Item No-19.1 PWD SR 2018-19	Cum	138.89	147.38	Rupees One Hundreden Thirty eight and paisa thirty eight only
2	KSRRB M 100-6, Crushing of stone boulders of 150 mm size in an integrated stone crushing unit of 200 Tonnes per hour capacity comprising of primary and secondary crushing units belt conveyor and vibrating screens to obtain stone aggregates of 13.2 mm nominal size including cost of materials equipments labour etc complete MORTH 100/Chapter -1	Cum	19.78	904.67	Rupees Nine Hundreden Four and paisa sixty seven only
3	KSRRB M 100-6, Crushing of stone boulders of 40 mm size in an integrated stone crushing unit of 200 Tonnes per hour capacity comprising of primary and secondary crushing units belt conveyor and vibrating screens to obtain stone aggregates of 40 mm nominal size including cost of materials equipments labour etc complete MORTH 100/Chapter -1	Cum	9.42	812.84	Rupees Eight Hundreden twelve and paisa eighty four only
4	KSRRB M 100-6, Crushing of stone boulders of 20 mm size in an integrated stone crushing unit of 200 Tonnes per hour capacity comprising of primary and secondary crushing units belt conveyor and vibrating screens to obtain stone aggregates of 20 mm nominal size including cost of materials equipments labour etc complete MORTH 100/Chapter -1	Cum	9.42	910.34	Rupees Nine Hundreden Ten and paisa thirty four only
5	KSRRB M-1200-46, Sand filling in wells complete as per drawing and technical specifications including cost of all materials labour HOM form works, scaffolding and centering complete as per specifications MORTH Specifications No-1207	Cum	9.42	3001.96	Rupees Three Thousand One and paise ninty six only
6	Disposal of debris to the final place of disposal with all lead and lift and as direction of the Engineer incharge of the work lead 4 kms Basic Rate for Rs 2.00 Tonne/Km b) Avarage earth of work 1.28 Tonne/Km for Rs 2.00/Km c) Add Loading and un loading	Cum	138.89	74.65	Rupees Seventy four and paise sixty five Only

p. n. s.

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palika
Dasarahalli Division, Bangalore - 560022

EIRL-1	KRSB 4.1.2, Providing and laying in position plain cement concrete of mix M10 with OPC Cement (a 220 kgs with 40 mm and down size graded granite metal course aggregate (a 0.892 cum and fine aggregate (a 0.465 cum machine mixed concrete laid in layers not exceeding 15 cms thick well compacted in foundation and plinth including cost of all materials,labour,HOM of machinery, curing etc complete as per specifications No;KBS 4.1.4.2	Cum	12.38	5669.69	Rupees Five thousand six hundreden sixty nine and paise sixty nine Only
EIRL-2	KRSB 4.1.3, Providing and laying in position plain cement concrete of mix M20 with OPC Cement (a 300 kgs with 20 mm and down size graded granite metal course aggregate (a 0.64 cum and fine aggregate (a 0.43 cum with super plastisicer (a 3 ltr conforming to IS 9103-1999 Reaffirmed -52008 machine mixed concrete laid in layers not exceeding 15 cms thick wall	Cum	11.09	6226.99	Rupees Six thousand two hundreden twenty six and paise ninety nine Only
EIRL-3	Providing and fixing granite benches including cost of materials labours as per specifications (Data Rate Approved)	Cum	22.00	18200.00	Rupees Eighteen thousand two hundre Only
EIRL-4	KSRB 4-6.4 Providing and removing centering and shuttering strutting propping etc and removal of form work for vertical surface such as walls at any thickness including attached plasters ,buttresses plinth,cills and string courses including cost of materials labours as per specifications specification No;KBS 4.6.2 P-16, I-4.31 PWD SR 2018-19	Nos	52.80	402.25	Rupees FourHundreden Two and paise twenty five only
EIRL-5	Loading and unloading	Sqm	138.89	69.80	Rupees sixty nine and paise eighty only
EIRL-6	Providing and to wall, ceiling and floor high density polythene pipes 6.00 kgs/sq.cms working pressure of outside diameter raising mains and exposed distribution pipes with special flange compression type fittings wall clips making good the wall ceiling,floor,including cost of all materials labour charges HOM and testing complete as	Cum	168.00	630.70	Rupees Six Hundreden thirty and paise seventy only
EIRL-7	Cost of RCC Pipes 1200mm Dia NP3 pipes	Mtr	15.00	8933.68	Rupees Eight thousand Nine Hundreden thirty three & Paise sixty eight only

Signature of the Contractor

Executive Engineer
 District Division
EXECUTIVE ENGINEER
 Bruhat Bangalore Mahanagara Palike
 Bangalore Division, Bangalore